BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/19/2017-18 Dated: 17-02-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 28

Name of Work:Maintenance of BBMP office Building in ward No- 02 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G.Muniraju	
				Rate	Rate in Words
1	Supplying of I Ball Scanner with all necessaory accories	Nos	1	10000.00	Rupees Ten Thousand Only
2	Supplying and fixing Canon Xerox machine for office use with all necessaory accories	Nos	2	98000.00	Rupees Ninety Eight Thousand Only
3	Supplying and fixing HP Colour jet Printer for office use with all necessaory accories	Nos	1	10000.00	Rupees Ten Thousand Only
4	Supplying and fixing UPS for office use with all necessaory accories	Nos	6	28000.00	Rupees Twenty Eight Thousand Only
5	Supplying of PROJECTOR with SCREEN and Television(LED) with all equipements for office use	Nos	1	98000.00	Rupees Ninety Eight Thousand Only
6	Providing and fixing 4"x1/2" size of beach wood design skirting with all necessaory accories	rmt	40	260.00	Rupees Two Hundred Sixty Only
7	Supplying and fixing Godrej Almera with all nesesaory accories	Nos	2	20000.00	Rupees Twenty Thousand Only
8	Fabricating, providing and erecting in position of MS Hot Dip Galvanised Sq Hallow Poles of 132 X 132 Heavy gauge of length 3000mm with MS. Hot dip Galvanised grill work as per approved design and drawing of chief architect. Using 12 X 75mm galvanised flat for alround frame and 20 X 20mm galvanised forged design with square for vertical at 150mm c/c as shown in the drawing including providing forged ornamental arrowhead at top and bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS. Hollow galvanized pipe, flats, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading and unloading with cost and conveyance of all materials, labour, machinery andincidental charges for the successful completion of the work as per the direction of the Engineer-in-charge of the work. (Data Rate)	sqm	25	9144.00	Rupees Nine Thousand One Hundred Forty Four Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G.Muniraju	
				Rate	Rate in Words
	Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq. rods and heads at top, middle and bottom. Intermediate supports of 75X12 mm and 50X6 mm arch bend to hot dip galvanised flats. The work is inclusive of throughing GI flat GI sq. rods, placing, welding all the joints including grinding, finishing metal putty, painting two coats enamel painting. The rate is inclusive of all materials like GI sq. pipe, GI sq. rods, GI forged designs etc., heavy duty hinges are made out of 75mm solid sq. block assembled with 20mm dia bearing in three places for each flop. Heavy Duty Locking arrangements at tow places including cost of labour, painting, erecting charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading, scaffolding charges and all other incidental charges for successful completion of the work as per directions of	Nos	9.60	12475.00	Rupees Twelve Thousand Four Hundred Seventy Five Only
10	KSRRB 300-1.Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no141, PWD SR 2016-17)	Cum	1.94	98.30	Rupees Ninety Eight and Paise Thirty Only
11	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2016-17	Cum	1.94	81.52	Rupees Eighty One and Paise Fifty Two Only
12	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2016-17)	Cum	0.32	5834.56	Rupees Five Thousand Eight Hundred Thirty Four and Paise Fifty Six Only
13	KSRB M2200-5.11.Design mix M20 with OPC cement @320 kgs,with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999 Reaffirmed-2008.etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no216,sno28.7.9)	Cum	1.73	8572.62	Rupees Eight Thousand Five Hundred Seventy Two and Paise Sixty Two Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G.Muniraju	
				Rate	Rate in Words
	5 mm thick plain glass(P.no XIII/S.no371 PWD SR 2016-2017)	Sqm	12.42	779.22	Rupees Seven Hundred Seventy Nine and Paise Twenty Two Only
15	Providing and fixing MS grill over exisiting compound wall as per using b16mmx16mm MS square rod at 150mm c/c spacing and 6mmx40mm MS flats at horizontal and 6mmx12mm MS flat for ornamtntal design and providing shp edge design at the verify of every vertical roads, incldung welding grinding hereve necessray All the steel surface should be throughly cleaned free of rust and paited with and ect.. as pers pecification(P.42/I.7.36 PW, P & IWTD-SR 2016-2017)	Sqm	2.88	6262.53	Rupees Six Thousand Two Hundred Sixty Two and Paise Fifty Three Only
16	Providing and fixing in position fully panelled Honne Wood shutters for doors, styles and rails of 40mm thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries Complete as per Specifications.	Sqm	3.24	5423.37	Rupees Five Thousand Four Hundred Twenty Three and Paise Thirty Seven Only
17	Applying priming coat over new wood surface and/ or wood based surface after preparing the surface after throughlycleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, completeas per specifications.	Sqm	6.48	49.15	Rupees Forty Nine and Paise Fifteen Only
18	Providing and Applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, clening the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications (P No. 102 Item No.15.60.1 PWD SR 2016-17)	Sqm	6.48	100.70	Rupees One Hundred and Paise Seventy Only
19	KSRB 13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 25 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads, complete as per specifications. Specification No. KBS 13.2.2/13.3 (Page No. 80 & Item No. 13.23).	Each	8	326.07	Rupees Three Hundred Twenty Six and Paise Seven Only
20	Supplying and fixing M.S. Rectangular Poles made but of 2 equal angles of 65 x 65 x 6 mm welded together and fixed inCC (1:2:4) with 2 Nos. 16 mm dia M. S. hold fast rods each of length 25 cms, including cost of all materials, cutting, bending scafoiding etc as per specifications. (P.No 37.2, 255)	Rmtr	10.80	981.82	Rupees Nine Hundred Eighty One and Paise Eighty Two Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.